

Report No.: AGC00742190601FE06

Page 106 of 125

15. FCC LINE CONDUCTED EMISSION TEST


15.1. LIMITS OF LINE CONDUCTED EMISSION TEST

F	Maximum RF Line Voltage				
Frequency	Q.P.(dBuV)	Average(dBuV)			
150kHz~500kHz	66-56	56-46			
500kHz~5MHz	56	46			
5MHz~30MHz	60	50			

Note:

- 1. The lower limit shall apply at the transition frequency.
- 2. The limit decreases linearly with the logarithm of the frequency in the range 0.15 MHz to 0.50MHz.

15.2. BLOCK DIAGRAM OF LINE CONDUCTED EMISSION TEST







Report No.: AGC00742190601FE06

Page 107 of 125

15.3. PRELIMINARY PROCEDURE OF LINE CONDUCTED EMISSION TEST

- 1. The equipment was set up as per the test configuration to simulate typical actual usage per the user's manual. When the EUT is a tabletop system, a wooden table with a height of 0.8 meters is used and is placed on the ground plane as per ANSI C63.10 (see Test Facility for the dimensions of the ground plane used). When the EUT is a floor-standing equipment, it is placed on the ground plane which has a 3-12 mm non-conductive covering to insulate the EUT from the ground plane.
- 2. Support equipment, if needed, was placed as per ANSI C63.10.
- 3. All I/O cables were positioned to simulate typical actual usage as per ANSI C63.10.
- 4. All support equipments received AC120V/60Hz power from a LISN, if any.
- 5. The EUT received charging voltage by adapter which received 120V/60Hzpower by a LISN.
- 6. The test program was started. Emissions were measured on each current carrying line of the EUT using a spectrum Analyzer / Receiver connected to the LISN powering the EUT. The LISN has two monitoring points: Line 1 (Hot Side) and Line 2 (Neutral Side). Two scans were taken: one with Line 1 connected to Analyzer / Receiver and Line 2 connected to a 50 ohm load; the second scan had Line 1 connected to a 50 ohm load and Line 2 connected to the Analyzer / Receiver.
- 7. Analyzer / Receiver scanned from 150 kHz to 30MHz for emissions in each of the test modes.
- 8. During the above scans, the emissions were maximized by cable manipulation.
- 9. The test mode(s) were scanned during the preliminary test.

Then, the EUT configuration and cable configuration of the above highest emission level were recorded for reference of final testing.

15.4. FINAL PROCEDURE OF LINE CONDUCTED EMISSION TEST

- EUT and support equipment was set up on the test bench as per step 2 of the preliminary test.
- 2. A scan was taken on both power lines, Line 1 and Line 2, recording at least the six highest emissions. Emission frequency and amplitude were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit. If EUT emission level was less –2dB to the A.V. limit in Peak mode, then the emission signal was re-checked using Q.P and Average detector.
- 3. The test data of the worst case condition(s) was reported on the Summary Data page.



Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,


Xixiang, Bao'an District, Shenzhen, Guangdong, China

Tel: +86-755 2523 4088 E-mail: agc@agc-cert.com Service Hotline: 400 089 2118



15.5. TEST RESULT OF LINE CONDUCTED EMISSION TEST

LINE CONDUCTED EMISSION TEST-L



MEASUREMENT RESULT: "TEST fin"

Frequency MHz	Level dBµV	Transd dB	Limit dBµV	Margin dB	Detector	Line	PE
0.322000 1.230000 2.258000 3.186000 7.698000 19.786000	33.50 22.20 22.50 23.00 14.80 26.90	10.2 10.4 10.4 10.4 10.6	60 56 56 56 60	26.2 33.8 33.5 33.0 45.2 33.1	QP	L1 L1 L1 L1 L1	FLO FLO FLO FLO

MEASUREMENT RESULT:

Frequency MHz	Level dBµV	Transd dB	Limit dBµV	Margin dB	Detector	Line	PE
0.322000	25.10	10.2	50	24.6	AV	L1	FLO
1.230000	14.80	10.4	46	31.2	AV	L1	FLO
2.266000	14.20	10.4	46	31.8	AV	L1	FLO
3.294000	14.60	10.4	46	31.4	AV	L1	FLO
7.706000	7.90	10.6	50	42.1	AV	L1	FLO
19.786000	20.30	11.0	50	29.7	AV	L1	FLO




Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,

Xixiang, Bao'an District, Shenzhen, Guangdong, China Tel: +86-755 2523 4088 E-mail:agc@agc-cert.com



LINE CONDUCTED EMISSION TEST-N



MEASUREMENT RESULT: "TEST fin"

Frequency MHz	Level dBµV	Transd dB	Limit dBµV	Margin dB	Detector	Line	PE
0.322000	32.10	10.2	60	27.6	QP	N	FLO
0.906000	27.60	10.4	56	28.4	QP	N	FLO
1.590000	26.90	10.4	56	29.1	QP	N	FLO
2.830000	26.60	10.4	56	29.4	QP	N	FLO
7.810000	19.70	10.6	60	40.3	QP	N	FLO
20.974000	24.30	11.1	60	35.7	QP	N	FLO


MEASUREMENT RESULT: "TEST_fin2"

Frequency MHz	Level dBµV	Transd dB	Limit dBµV	Margin dB	Detector	Line	PE
0.322000	20.50	10.2	50	29.2	AV	N	FLO
0.910000	17.00	10.4	46	29.0	AV	N	FLO
1.590000	17.20	10.4	46	28.8	AV	N	FLO
2.830000	16.20	10.4	46	29.8	AV	N	FLO
7.810000	10.20	10.6	50	39.8	AV	N	FLO
20.974000	15.20	11.1	50	34.8	AV	N	FLO

RESULT: PASS



 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$






APPENDIX A: PHOTOGRAPHS OF TEST SETUP

FCC LINE CONDUCTED EMISSION TEST SETUP



FCC RADIATED EMISSION TEST SETUP BELOW 1GHZ






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,

Xixiang, Bao'an District, Shenzhen, Guangdong, China Tel: +86-755 2523 4088 E-mail:agc@agc-cert.com






FCC RADIATED EMISSION TEST SETUP ABOVE 1GHZ





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$






APPENDIX B: PHOTOGRAPHS OF EUT TEST MODE -XHT-6B16

ALL VIEW OF EUT





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$





TOP VIEW OF EUT




BOTTOM VIEW OF EUT





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,





FRONT VIEW OF EUT




BACK VIEW OF EUT





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$





LEFT VIEW OF EUT




RIGHT VIEW OF EUT






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,






OPEN VIEW OF EUT 1




OPEN VIEW OF EUT 2






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,






INTERNAL VIEW OF EUT-1




INTERNAL VIEW OF EUT-2





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,





VIEW OF PORT -1




VIEW OF PORT -2





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$






Series Model- XHT-6B18

ALL VIEW OF EUT






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$





TOP VIEW OF EUT




BOTTOM VIEW OF EUT





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,





FRONT VIEW OF EUT




BACK VIEW OF EUT





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,





LEFT VIEW OF EUT




RIGHT VIEW OF EUT






Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,






OPEN VIEW OF EUT 1




INTERNAL VIEW OF EUT-1






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,





INTERNAL VIEW OF EUT-2




VIEW OF PORT-1





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,





VIEW OF PORT-2



----END OF REPORT---



 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$